



Home in Greystones Co. Wicklow, Ireland

Parkland Construction wanted to install a heat pump but did not want to bore holes in the ground. They also wanted UFH on both floors. Hotfoot had the solutions with the Octopus Ice Stick, Optiheat UFH and Maxxon Floor Screed all in one installation.

FACTS:

- 175 sqm Built 2007
- OptiHeat UFH pipes on both floors covered with 20mm floor screed (www.maxxon.ie)
- An IS 48 Split was installed with a central unit
- House is at a constant 21 degrees
- From 5/09/08-5/09/09 the heating consumed 5417kWhrs at a cost of €574 + vat.
- The key figure is 31kWhrs/sqm



Hotfoot (UK)
1 Joseph Rich Court
New St. Oakengates
Telford, Shropshire
TF2 6ES
Tel: +44 121 288 3377
Mob: +447900516982

Hotfoot (Ireland)
58 Newtown Business
& Enterprise Park
Newtownmountkennedy,
Co. Wicklow
Ph: +35312871172
Mob: +353868277708

Hotfoot (Canada)
262 Roncesvalles,
Toronto,
Ontario
M6R 2M1
Mob: +14168789348

